



EASTERN POWER DISTRIBUTION COMPANY OF A.P. LTD.  
CORPORATE OFFICE::VISAKHAPATNAM

Memo.No:Dir/Projects/CGM/QC/GM/QC/F.DOC/D.No: 978 /10 Dt: 06 -09-2010

Sub: EPDCL-QC Wing- Certain guidelines for construction of plinth for erection of DTRs – Reg.

Ref : LR.No: CGM/QC/GM/QC/F.DOC/D.No: 932 /10 Dt: 23 -08-2010

\*\*\*

Further to this office memos under references cited the following amendments are issued to the instructions already communicated.

Sl. No	Description of the equipment	Size of the Plinth
1	Distribution transformers capacity Above <del>6 KVA</del> upto 160 KVA	4' x 4' x 9' Height 6' above ground level and 3' below ground level with first class bricks and with C.M 1 : 5 (or) with quality R.R.Stone and with C.M 1 : 5 (or) <b>Erection of DP Structure (Double Pole) with 9.1 Mts PSCC Poles</b>
2	Distribution transformers capacity 40 KVA and lower capacity	Single pole structure complete for mounting of 3 Phase transformer with 9.1 Mts PSCC Pole

B  
8/2/10

Stamp: CGM/PROJECTS QC & IT  
CGM/QC  
GM/IT  
D.S. 12  
3-12

Handwritten: *whentate*  
*AB/De*  
*de*  
*08/09/10*

The above instructions are issued duly superceding all the earlier orders issued in this regard.

The Superintending Engineer/Operation are requested to follow the above instructions without any deviations.

*hmsg*  
Director/Projects  
AEPDCL :: Visakhapatnam

To  
All Superintending Engineers/Operation/  
Copy to  
All AAE/AEs/Operation /AEPDCL/  
All ADEs/Operation /AEPDCL/  
(Through DE/Operation)  
All Divisional Engineers/Operation /AEPDCL/  
are instructed to serve the memo in duplicate and obtain dated acknowledgement  
DGM/IT/EPDCL/VSP... is instructed to put the memo in EPIMRS Dashboard  
DGM/CC/EPDCL/VSP... is instructed to put the memo in our Web site  
EE/Civil/Corporate Office/VSP  
CGM/O&CS/EPDCL/Visakhapatnam  
CGM/Projects/EPDCL/Visakhapatnam  
CGM/Tech-CMD/EPDCL/Visakhapatnam  
*Copy submitted to the Director/operation/EPDCL/VSP for favour of information.*